

QUOTATION OF UNDERGROUND WATER TANK

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	Excavation: Excavate round underground water tank not exceeding 16m deep	384	m ³	15,600	5,990,400
2	Block work: Construct wall 230mm thick with special concrete block binded with cement and sand (mix 1:4) with water proof cement	320	m ²	34,600	11,072,000
3	Re-bars: Reinforcement beams and columns				
	Y16	627	Kg	3,500	2,194,500
	Y12	212	Kg	3,500	742,000
	Y8	208	Kg	3,500	728,000
4	Formwork: Supply and fit plywood 12mm thick and 4x2 timber	73	m ²	11,400	832,000
5	Concrete work: Reinforcement concrete to		m ³		
	Beams	10		360,000	3,600,000
	Slab	6	m ³	360,000	2,160,000
6	Finnishing: Apply cement and sand moter (mix 1:2) with water proof cement	320	m ²	14,300	4,576,000
7	Ladder: Fabricate steel fixed ladder with safety protection	1tm		1,400,000	1,400,000
8	Cover: Fabricate steel metal cover to hurch with lock	1tm		120,000	120,000
GRAND TOTAL AMOUNT					33,414,900